COLUMN & WALL SCHEDULE

COL. No. / DATA	f'c		A 2	A 3	A 3y			A.4–B.6		A 7		A 9		Ax 2		Ax 3		Ax 7–8	Ax 9		C 2	C 3			C 5			C 8	C 10		C 11		D.2–D.3y	D.3y–D.5	D.3y–Dx.3y	D.5–Dx.5	Dx.3y–Dx.4		E.2–E.5		D.6–D.11	E.6–E.11		COL. No. / DATA
UPPER ROOF																																													UPPER ROOF
4150 PENTHOUSE	16~30 MPa																																												4350 PENTHOUSE
3370 14TH FLOOR																																													3470 14TH FLOOR
3250 13TH FLOOR																																													3250 13TH FLOOR
2950 12TH FLOOR																																													2950 12TH FLOOR
3050 11TH FLOOR																																													3050 11TH FLOOR
2950 10TH FLOOR																																													2950 10TH FLOOR
3050 9TH FLOOR																																			200 WALL ADD 4–20 VEE ▲	200 WALL ADD 4–20 VEE ▲	200 WALL ADD 4–20 VEE ▲								3050 9TH FLOOR
2950 8TH FLOOR																					450x450 8–20	300x600 6–20			300x600 6–20			300x600 6–20	300x600 6–20		450x450 8–20		200 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲ ADD 2–20 ALL AROUND THE OPENING	300 WALL ADD 4–20 VEE ▲		200 WALL ADD 4–20 VEE ▲		200 WALL ADD 4–20 VEE ▲	200 WALL ADD 4–20 VEE ▲		2950 8TH FLOOR
2950 7TH FLOOR																																			300 WALL ADD 4–20 VEE ▲												2950 7TH FLOOR
2950 6TH FLOOR																									300x600 6–20										300 WALL ADD 4–20 VEE ▲												2950 6TH FLOOR
3050 5TH FLOOR																600x300 6–20		600x300 6–20			450x450 8–20	300x600 6–20			200 WALL 10Φ300 HEF 10Φ400 VEF ADD 2–20HΦ T&B ADD 4–20 VEE ▲			300x600 6–20	300x600 6–20				300 WALL 10Φ200 HEF 10Φ270 VEF ADD 4–20HΦ T&B ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲ ADD 2–20 ALL AROUND THE OPENING	300 WALL ADD 4–20 VEE ▲		200 WALL ADD 4–20 VEE ▲					3050 5TH FLOOR
2790 4TH FLOOR			450x450 8–20	300x600 6–20	300x600 6–20			200 WALL ADD 4–20 VEE ▲		300x600 6–20		300x600 6–20		900x250 8–20					600x300 6–20		200 WALL ADD 4–20 VEE ▲			BEAM	200 WALL ADD 4–20 VEE ▲		200 WALL					200 WALL ADD 4–20 VEE ▲		300 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲	300 WALL ADD 4–20 VEE ▲		200 WALL ADD 4–20 VEE ▲		200 WALL ADD 4–20 VEE ▲	200 WALL ADD 4–20 VEE ▲		2790 4TH FLOOR
2790 3RD FLOOR			450x450 8–20	300x600 6–20				200 WALL ADD 4–20 VEE ▲													200 WALL ADD 4–25 VEE ▲				200 WALL ADD 4–25 VEE ▲		200 WALL					200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲		300 WALL ADD 4–25 VEE ▲	300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲	300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲		200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲		200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲	200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ TOP ADD 4–25 VEE ▲		2790 3RD FLOOR
3250 2ND FLOOR			250 WALL ADD 4–20 VEE ▲	300x600 6–20				200 WALL 10Φ200 HEF 10Φ400 VEF ADD 4–20HΦT&B ADD 4–20 VEE ▲		300x600 6–20		300x600 6–20		900x250 8–20		600x300 6–20		600x300 6–20	600x300 6–20		200 WALL 10Φ200 HEF 10Φ300 VEF ADD 4–20HΦ TOP & BOT ADD 4–25 VEE ▲			200 WALL 10Φ200 HEF 10Φ300 VEF ADD 4–25 VEE ▲			200 WALL 10Φ200 HEF 10Φ300 VEF ADD 4–25HΦ T&B ADD 4–25 VEE ▲		200 WALL		450x450 8–20			200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲		300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲	300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲	300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲		200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲		200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲	200 WALL 15Φ300 HEF 10Φ300 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲		3250 2ND FLOOR
4250 GROUND	16~35 MPa		250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–20HΦ T&B ADD 4–20 VEE ▲	BEAM 300x600 6–20				BEAM 250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–20HΦ T&B ADD 4–25 VEE ▲	BEAM 300x600 6–20	BEAM 300x600 6–20	BEAM 300x700 8–20	BEAM 300x700 8–20		BEAM 900x250 8–20	BEAM 200 WALL ADD 4–20HΦ T&B ADD 4–20 VEE ▲		BEAM	BEAM 700x300 8–20		250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–20HΦ T&B ADD 4–25 VEE ▲	BEAM		SLAB		BEAM 250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–25HΦ T&B ADD 4–25 VEE ▲		BEAM 400x800 10–30			SLAB 300 WALL 15Φ300 HEF 10Φ270 VEF ADD 4–25HΦ BOT ADD 4–25 VEE ▲	SLAB	SLAB 250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–20HΦ T&B ADD 4–25 VEE ▲	BEAM 400x800 10–30		250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–25HΦ T&B ADD 4–25 VEE ▲	BEAM 250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–20HΦ T&B ADD 4–25 VEE ▲	250 WALL 15Φ300 HEF 10Φ200 VEF ADD 4–25HΦ T&B ADD 4–25 VEE ▲		4250 GROUND
EL. 0.000			SLAB		SLAB			SLAB		SLAB		SLAB		SLAB	SLAB			SLAB	SLAB		SLAB									SLAB		SLAB			SLAB									EL. 114.75
DATA / COL. No.	f'c		A.2–A.3		A 3y			Ax.4–B.8		A 6		A 8	A 9			Ax 2	Ax–3	Ax 7–8	Ax 9		C.2–C.3y				C.5–Cx.5			C.6–C.10		C.9–C.13		D 2	D.3y–D.5	D.3y–Dx.3y	D.5–Dx.5	C–3y/4 X F–3y/4		E 2		D.9–D.13	C.8–Ex.8	E.9–E.13		DATA / COL. No.

Jablonsky, Ast and Partners
CONSULTING ENGINEERS
1129 LESLIE STREET
DON MILLS, ON., M3C 2K5
TEL 416-447 7405
FAX 416-447 2771
E-mail jap@astnt.on.ca

P.F. AST
13015
PROVINCE OF ONTARIO

FIRST FLOOR ELEV. 93.60m

no.	issued / revised	date:
1	ISSUED FOR PERMIT	2014-05-30
2	RE ISSUED FOR PERMIT	2014-07-10
3	ISSUED FOR FORMING TENDER	2014-08-27
4	CONSTRUCTION REVIEW	2014-12-15
5	RE ISSUED FOR PERMIT	2015-01-27
6	ISSUED FOR CONSTRUCTION	2015-03-16
7	UPDATED - IFC	2015-04-20
8	UPDATED - IFC	2015-05-21
9	ISSUED FOR SI-9	2015-07-28

ALEXANDRA PARK - BLOCK 11
TORONTO, ONTARIO

project no: 13015
scale: AS NOTED
drawn by: H.W.
reviewed by: H.P.
date started: MARCH 2014

COLUMN & WALL SCHEDULE

S-202

2015-07-28

1219x914

C:\Projects\13015 ALEXANDRA PARK BLOCK-11\STRUCTURE\S-201-S-205 COL &WALL.dwg, 2015-07-28 9:45am

C:\Projects\13015 ALEXANDRA PARK BLOCK-11\STRUCTURE\S-201-S-205 COL &WALL.dwg, 28/07/2015 9:45:24 AM, 11191 (914.00 x 1220.00 MM), Helen